

12-29

242

4-041439

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-167-22,846-00-00

SE SW NW /4 SEC. 27, 11 S, 15 W
2970 feet from S section line
4290 feet from E section line

Operator license# 5140 Lease Seattle-Pacific well # 1

Operator: Frontier Oil Company County Russell

Address: 125 N. Market Well total depth 3317 feet 107.80
Suite 1720 Conductor Pipe: 0 inch @ 0 feet'
Wichita, Kansas 67230 Surface pipe 8 5/8 Inch @ 237 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:00A.M. Day: 29 Month: December Year: 92

Plugging proposal received from: Richard Parker

Company: Frontier Oil Company Phone: 913-483-5348

Were: 4 1/2" casing set @ 3316' w/175 sx. cement. Perf. 3188' -
3196'. D.V. @ 902' w/300 sx. circ. cement. W.L.M. 3180'.
Order 250 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:15P.M., Day: 29, Month: December, Year: 92

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped in 250 sx.
cement with 1/4# flocele plus 300# hulls mixed in cement.
Max. 1000# P.S.I. S.I. 600# P.S.I. Hooked-up to 8 5/8" S.P.
Pressured-up to 500# P.S.I.

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 17 1993
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X NO
Plugged through TUBING , CASING X. Elevation: GL

I did XY did not] observe the plugging. Dennis L. Hamel

INVOICED
DATE 1-25-93
37229

HO. (agent)
Form CP-2/3