

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21211-00-00
Spot: NENWNW Sec/Twnshp/Rge: 31-8S-28W
525 feet from N Section Line, 830 feet from W Section Line
Lease Name: COOPER Well #: 2
County: SHERIDAN Total Vertical Depth: 4150 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	250		

134.88

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/02/2008 10:00 AM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: RITA ANDERSON Company: CASTLE RESOURCES, INC. Phone: (78) 625-5155

Proposed Plugging Method: Ordered 205 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 12/02/2008 11:45 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st. Plug at 2430' w/25 sxs. 2nd. Plug at 1600' w/100 sxs. 3rd. Plug at 300' w/40 sxs. 4th. Plug at 40' w/10 sxs. Rathole with 30 sxs.
--

Perfs:

INVOICED
DATE 1-13-09
INV. NO. 2009060967

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 09 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.
Plugged through: DP

District: 04 Signed CASE MORRIS
(TECHNICIAN)

DEC 08 2008

PKT