

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-073-24005-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 19-22S-10E  
2310 feet from S Section Line, 660 feet from E Section Line  
Lease Name: BROWNING Well #: 22  
County: GREENWOOD Total Vertical Depth: 2355 feet

Operator License No.: 30471  
Op Name: EDGEWOOD LAND AND CATTLE CO.  
Address: 338 MIDDLE CREEK RD  
ELMDALE, KS 66850

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2355	560	170 SX
SURF	8.625	204		120 SX CMT CLASS A 3% CALC, 2 SX GEL

76.54

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/18/2008 8:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: HARRY PATTERSON OR G Company: \_\_\_\_\_ Phone: (316) 733-2248

Proposed Plugging Method: SHOOT OFF PIPE AT 450' PLACE 60 SK CEMENT ON BOTTOM, PLACE 25 SK CEMENT AT 450' FROM 150' TO TOP.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/20/2008 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2300' pumped 60 sxs cement , pulled tubing out,shot casing @450' pumped 25 sxs cement, pulled casing to 150' circulted cement to surface,gel spacers between cement plugs, 560' casing recovered.

RECEIVED  
KCC DISTRICT #3  
DEC 08 2008  
CHANUTE, KS

MH

Perfs:

Top	Bot	Thru	Comments
2324	2328		
2312	2318		

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 10 2008  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 1-13-09  
INV. NO. 2009060971

Remarks:  
Plugged through: CSG

District: 03 Signed Michael Heffern  
(TECHNICIAN)

PKT