

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-23987-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 19-22S-10E
330 feet from S Section Line, 2000 feet from E Section Line
Lease Name: BROWNING Well #: 20
County: GREENWOOD Total Vertical Depth: 2473 feet

Operator License No.: 30471
Op Name: EDGEWOOD LAND AND CATTLE CO.
Address: 338 MIDDLE CREEK RD
ELMDALE, KS 66850

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2474	720	200sx
SURF	8.625	204		110sx
T1	2.375	2436		

80.37

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/18/2008 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: HARRY PATTERSON OR G Company: _____ Phone: (316) 733-2248

Proposed Plugging Method: SHOOT OFF PIPE AT 900' PLACE 60 SK CEMENT ON BOTTOM, PLACE 25 SK CEMENT AT 900'. CEMENT FROM 150' TO TOP.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 09/20/2008 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2450' pumped 60 sxs cement pulled tubing out shot casing @ 900' pumped 25 sxs cement, pulled casing to 150' circulated cement to surface, gel spacers between cement plugs 720' casing recovered.

Perfs:

Top	Bot	Thru	Comments
2456	2462		

INVOICED
DATE 1-13-09
INV. NO. 2009060971

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 10 2008
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KCC DISTRICT #3

DEC 08 2008

CHANUTE, KS

MT

Remarks:

Plugged through: CSG

District: 03

Signed Mike B
(TECHNICIAN)

PKS