

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19741-00-00
Spot: SESESW Sec/Twnship/Rge: 20-23S-4E
247 feet from S Section Line, 2991 feet from E Section Line
Lease Name: PARRIS Well #: 1
County: BUTLER Total Vertical Depth: 2083 feet

Operator License No.: 7131
Op Name: MORRIS, RICHARD B.
Address: PO BOX 482
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2046		50 SX
SURF	8.625	62		40 SX

67.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2008 12:00 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD B. MORRIS Company: RICHARD B MORRIS Phone: (620) 628-4777

Proposed Plugging Method: SAND TO 1960' W/4 SXS CEMENT ON TOP. CIRCULATE FROM 250' TO SURFACE

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2008 6:35 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:
RIH W/WORKSTRING @ 1917', CONSOLIDATED MIXED & PUMPED 50 SXS CLASS A 4% GEL, 3% CC AND DISPLACED IN CASING. RIW W/WORKSTRING @ 253', & 1" ON BACKSIDE OF 4-1/2" @ 249' CONSOILDATED SWEDGED INTO 1" AND MIXED AND PUMPED 138 SXS CLASS A 4% GEL TO SURFACE. CEMENT CIRCULATED UP BACKSIDE OF 4-1/2" CASING. INSIDE 4-1/2" CASING AND INSIDE 2-3/8" WORKSTRING TO SURFACE. SWEDGED INTO WORKSTRING AND PUMPED ADDITIONAL 10 SXS. LAYED DOWN WORKSTRING & 1", TOPPED WELL OFF. P.A. COMPLETE 6:35 P.M. 11/17/2008.

Perfs:

Top	Bot	Thru	Comments
2043	2047		
2018	2030		

INVOICED
DATE 1-13-09
INV. NO. 2009060975

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 09 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: CONSOLIDATED CEMENT TICKET #19630
Plugged through: TBG

District: 02 Signed Duane Krueger (TECHNICIAN) PKS