

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-19631-00-00
Spot: NWSESESE Sec/Twnshp/Rge: 29-30S-16E
400 feet from S Section Line, 400 feet from E Section Line
Lease Name: UNIT 1- ELLIS Well #: ELLIS 4
County: WILSON Total Vertical Depth: 837 feet

Operator License No.: 3830
Op Name: A X & P, INC.
Address: PO BOX 1176
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.875	751		
SURF	8.625	30		
T1	2	732	450	35'

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2006 8:00 AM
Plug Co. License No.: 3830 Plug Co. Name: A X & P, INC.
Proposal Rcvd. from: J J HANKE Company: A X & P, INC. Phone: (620) 331-0144

Proposed Plugging Method: Remove pipe strings from well and pump full of cement utilizing gel spacers.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 11/06/2006 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The 1" pumping string and pump were removed. 450' of the 2" pipe was removed. The well was then perforated at 250', 125', and 75'. A 1" cement string was lowered to TD and the bottom plug was spotted. The cement string was raised to 250' and the well pumped full of cement to surface. Gel spacer was used between plugs. A total of 110 sacks of portland cement were used to plug well.

Perfs:

INVOICED
DATE 1-15-09
INV. NO. 2009061007

RECEIVED
KCC DISTRICT #3
DEC 9 2008 AMD
CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)