

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22068-00-00
Spot: SENENW Sec/Twnshp/Rge: 4-15S-13W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HEFFERNAN Well #: 1
County: RUSSELL Total Vertical Depth: 3248 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 W WICHITA AVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3248	0	w/255 sxs cmt
SURF	8.625	722	0	w/350 sxs cmt

105.56

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2008 2:00 PM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: FRANK SCHULTE Company: BENNETT & SCHULTE OIL COMPA Phone: (785) 635-2626

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 600# hulls - 6 sxs gel.
CIBP at 2940'. Perfs at 300' - 700' - 1350'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2008 5:15 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2930' - pumped 75 sxs cement with 200# hulls.
Pulled tubing to 1900' - pumped 6 sxs gel.
Pulled tubing to 1350' - pumped 200 sxs cement with 400# hulls - cement circulated.
Pulled tubing out - topped off with 35 sxs.
Hooked to braden head and pumped 15 sxs cement.
Max. P.S.I. 150#.

Perfs:

INVOICED
DATE 1-15-09
INV. NO. 2009061008

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 17 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #1078.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM
Form CP-2/3
[Signature]

DEC 15 2008

AMES OIL COMPANY

P.O. BOX 1309

HAYS, KS 67601

#1 HEFFERNAN

4-15-13W

SE NE NW

CONTR RED TIGER DRILLING CO. CTY RUSSELL


GEOL CHARLES RHOADES FIELD TRAPP

ELV 1745 KB SPD 1/18/83 CARD ISSUED 5/12/83 IP OIL WELL

1740 GL

API 15-167-22,068

WAB (TARK) 2285-2387 OA
SHAW (TOR) 2907-2911



LOG	Tops	Depth/Datum
ANH		711 + 1034
TARK SD		NOT AVAILABLE
TARK		2342- 597
TOP		2640- 895
TOR		2869-1124
LKC		2917-1172
BKC		3179-1434
CONG		3207-1462
ARB		3225-1480
RTD		3248-1503

8 5/8 " 722/350SX; 5 1/2 " 3248/255SX
 DST (1) 2850-2970 (TOR, LKC) / 30-60-30-60, REC 30' M, NS,
 SIP 715-658#, FP 100-134#, HP 1593-1550#, BHT 99°
 MICT - CO, PF (CONG) 3218-20, SWB DWN & REC ALL WTR,
 770' FROM SURF, SET CIBP AT 3188', PF (LKC) 3168-70, 3146-
 50, 3113-16, 3103-06, AC 2000G, SWB DWN & REC 2 BFPH
 (50% OIL), PF (LKC) 2994-96, AC 300G (MA), SWB DWN & REC
 3 BFPH (TR OIL), PF (LKC) 2954-58, AC 5000G, SWB DWN & REC
 4.50 BFPH (20% OIL), SET BP AT 2940', PF (TOR) 2907-11, FRAC
 15,000# SD & FL, SWB DWN & REC 23 BFPH (7.5% OIL), PF
 (TARK) 2383-87, FRAC 15,000# SD & FL, SWB DWN & REC 40
 BFPH (14% OIL), PF (TARK SD) 2305-09, 2285-89, FRAC
 15,000# SD & FL, SWB DWN & REC 36 BFPH (14% OIL), POP, 3/
 9/83, COMMINGLED (LKC PAY REMAINS BEHIND PIPE)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS