

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20481-00-00
Spot: SESE Sec/Twnshp/Rge: 12-31S-32W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: WHITNEY Well #: 1
County: SEWARD Total Vertical Depth: 5560 feet

Operator License No.: 3855
Op Name: P & M PETROLEUM MANAGEMENT, L.L.C
Address: 518 17TH ST STE 1105
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5200		WITH 2 SX CMT
PROD	4.5	5550	0	WITH 250 SX CMT
SURF	8.625	1521		WITH 650 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/11/2008 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: IRVIN MORSE Company: P & M PETROLEUM Phone: (303) 260-7129

Proposed Plugging Method: CIBP @ 5200' WITH 2 SX CMT. PERFORATE @ 1600' & CMT SQUEEZE CMT USING A RETAINER INSIDE & OUTSIDE OF CASING TO SURFACE.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2008 10:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 5200' WITH 2 SX CMT. PERFORATE 4 1/2" @ 1600'. CMT RETAINER @ 1500'. PUMPED 135 SX CMT THROUGH RETAINER. NO BLOW OR SUCK ON ANNULUS. PULLED OUT OF RETAINER. PUMPED 30 SX CMT ON TOP OF RETAINER. PERFORATE @ 600'. PUMP 200 SX CMT THROUGH 4 1/2" CASING. CIRCULATED TO SURFACE. 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL.

Perfs:

Top	Bot	Thru	Comments
5341	5345		


INVOICED
DATE 1-15-09
INV. NO. 2009061020

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 19 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Jack MacLashy
(TECHNICIAN)