

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20377-00-01
Spot: SESWSE Sec/Twnshp/Rge: 19-11S-20W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: VANCE OWWO Well #: 1
County: ELLIS Total Vertical Depth: 3870 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3038		
CIBP		3430		
PROD	4.5	3869	0	175 SX
SURF	8.625	208	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2008 10:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GERALD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-9571

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Drilled out approximately 1510'. There is another hole at 1328'.
Squeeze hole at 650'. Tubing and packer in the hole at 1890'.
Model R Packer at 1980'. CIBP at 3430'. Cement plug at 3038'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2008 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 1478' - rigged to tubing - pumped 190 sxs cement with 300# hulls.
Pulled tubing to 787' - rigged to tubing - pumped 40 sxs cement with 200# hulls to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge - pumped 10 sxs cement.
Max. P.S.I. 275#. S.I.P. 200#.
Rigged to 8 5/8" - pumped 30 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3513	3714		

INVOICED
DATE 1-15-09
INV. NO. 2009061001

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 16 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #28950.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

PRT

A. SCOTT RITCHIE & GLICKMAN, INC.
 125 N. MARKET, #950 #1 VANCE "OWWO"
 WICHITA, KS 67202

19-11-20W
 SE SW SE

CONTR BLUE GOOSE DRILLING, INC. CTY ELLIS

GEOLOGICAL FIELD NICHOLSON EXT (1/4 N)

	+	+
	+	+
	+	+

FLV 2229 KB SPD 6/26/84 CARD ISSUED 1/3/85 IP P 15 BO & 85 BWPD
 LKC 3513-3714 OA

LOG	Tops	Depth Datum
ANIT	1641 F 588
TOP	3255-1026
OH	3406-1177
HEEB	3472-1243
TOR	3496-1267
LKC	3512-1283
MARM	3792-1563
ARB	3825-1596
RTD	3870-1641
LTD	3872-1643

API 15-051-20,377-A
 OLD INFO: OPERATOR WAS GLICKMAN-EXECUTIVE PETROLEUM.
 #1 VANCE, SPD 12/18/68, SET 8 5/8 " 208 / 150GX, COMP AS D
 & A / ARB (CARD ISSUED 1/9/69). CONTR: B & R DRILLING.
 GEOL: FRANK BROOKS
 DST (1) 3370-3380 (TOP) / OP 60", REC 70' WTRY MUD, SIP
 1120-1073#, FP 21-47#
 DST (2) 3410-3442 (OH) / OP 90", REC 70' SOGM, 30' SOGMW,
 SIP 1089# / 60" - 1047# / 60", FP 26-58#
 DST (3) 3501-3530 (TOR, LKC) / OP 105", REC 40' MUD, & SPRKS
 OIL, SIP 1078# / 45", 1047# / 60", FP 26-36#
 DST (4) 3536-3560 (LKC) / OP 75", 200' GIP, REC 10' O & GCM,
 180' M & GCO, SIP 860-528#, FP 31-73#
 DST (5) 3560-3602 (LKC) / OP 90", 80' GIP, REC 130' O & GCM,
 120' O & GCMW, SIP 328-328#, FP 52-164#
 (over)

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

A. SCOTT RITCHIE & GLICKMAN, INC. #1 VANCE "OWWO"

19-11-20W
 SE SW SE

DST (6) 3662-3700 (LKC) / OP 90", 100' GIP, REC 100' HO & GCM, SIP 370-307#, FP 26-47#
 DST (7) 3700-3720 (LKC) / OP 90", REC 55' MUD W / SP O, SIP 923-891#, FP 31-42#
 DST (8) 3820-3837 (MARM, ARB) / OP 90", REC 150' MUD, 60' WTRY MUD, SIP 1063-1016#, FP 95-126#
 NO CORES
 NEW INFO: FR 6/25/84, RE-ENTERED 6/26/84, WSH DWN TO ORTD, SET 4 1/2 " 3869/175SX, MICT - CO, PF
 (LKC) 3684-97, 3674-78, 3710-14, W/ 2 SPF, AC 1850G (28% NE), SWB LD, SO, PF (LKC) 3553-56, W/ 2 SPF,
 AC 600G (28% NE), SWB LD, SO, PF (LKC) 1/ 3597, 1/ 3590, AC 800G (28% NE), SWB LD, SO, PF (LKC) 3597-
 99, 3590-92, 3572-76, 3513-16, W/ 2 SPF, AC 1250G (28%) FROM 3576-97, AC 1000G (28%) FROM 3513-16,
 SWB LD, SO, POP, P 15 BO & 85 BWPD 9/26/84