

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22361-00-00  
Spot: SWNENE Sec/Twnshp/Rge: 19-34S-13W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: L L DEWITT Well #: 2  
County: BARBER Total Vertical Depth: 4940 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4920	2910	WITH 150 SX CMT
SURF	8.625	217		

160.55

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/07/2009 2:30 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4760' & 4 SX CMT. PLUG AT 700' WITH 10 SX GEL-50 SX CMT-100# HULLS. PLUG AT 250' WITH 50 SX CMT-100# HULLS. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/07/2009 3:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4760' & 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PLUG THROUGH 4 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL-50 SX CMT-100# HULLS. 2ND PLUG AT 250' WITH 50 SX CMT & 100# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4815	4830		


INVOICED  
DATE 2-5-09  
INV. NO. 2009061165

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 21 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING

Plugged through: CSG

District: 01



Signed

Stephen J Pfeifer  
(TECHNICIAN)