

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23082-00-00
Spot: NWNWSW Sec/Twnshp/Rge: 1-32S-10W
2310 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HALPHEN Well #: 1-1
County: BARBER Total Vertical Depth: 4537 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4536	3275	WITH 130 SX CMT
SURF	8.625	257		WITH 225 SX CMT <u>147.45</u>

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/19/2008 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 4310' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 70 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 12/19/2008 11:30 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

SAND TO 4310' WITH 4 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG PULL CASING TO 290' & PUMP 70 SX CMT. 3RD PLUG PULL CASING TO 40' & PUMP 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4364	4376		

INVOICED
DATE 2-5-09
INV. NO. 2009061165

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 21 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: CSG

District: 01

RECEIVED
JAN 16 2009
KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN)

Handwritten initials