

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-21449-00-00  
Spot: S2NWSE Sec/Twnshp/Rge: 35-29S-35W  
1680 feet from S Section Line, 1900 feet from E Section Line  
Lease Name: MERRITT MLP Well #: 1-35  
County: GRANT Total Vertical Depth: 5700 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		3010		WITH 75 SX CMT
PROD	4.5	5692	1789	WITH 265 SX CMT
SURF	8.625	1812		WITH 700 SX CMT

185.25

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/20/2009 8:00 AM  
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC  
Proposal Rcvd. from: BARRY Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: CIBP @ 5250' & 2 SX CMT OR PUMP 200# HULLS & 25 SX CMT. CIBP @ 3100' & 2 SX CMT OR PUMP 25 SX CMT AT 3030'. RIH WITH TBG TO 1830'. LOAD HOLE WITH MUD & PUMP 50 SX CMT. PULL TO 660' CIRCULATE CM TO 0'.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/20/2009 4:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT AT 5303'. 1ST PLUG AT 3340' WITH 25 SX CMT. 2ND PLUG AT 1850' WITH 50 SX CMT. 3RD PLUG AT 660' WITH 200 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5595	5606		CHESTER
5303	5306		MORROW (SQUEE)

INVOICED  
DATE 2-5-09  
INV. NO. 2009061165

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 29 2009

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 01

RECEIVED

JAN 27 2009

KCC DODGE CITY

Signed

Jack MacLaskey  
(TECHNICIAN)

Form CP-2/3