

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22457-00-00
Spot: E2SWNW Sec/Twnshp/Rge: 4-9S-20W
3304 feet from S Section Line, 4386 feet from E Section Line
Lease Name: ARPIN Well #: 1
County: ROOKS Total Vertical Depth: 3735 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3718	0	w/100 sxs cmt
SURF	8.625	246	0	w/140 sxs cmt
T1	2	3731		

121.39

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/20/2009 11:30 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: OZZIE VAN AUSDALE Company: OIL PRODUCERS INC. OF KANSAS Phone: (785) 623-3014

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.
Squeezes at 1550' - 1740' w/175 sxs; 943' w/100 sxs.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2009 1:40 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3500' - pumped 65 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 2500' - pumped 65 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled tubing to 1500' - pumped 115 sxs 60/40 pozmix - 4% gel with 100# hulls to circulate to surface.
Pulled all tubing - pumped 10 sxs 60/40 pozmix - 4% gel.
S.I.P. 500#.
Backside pressured to 350# immediately.

Perfs:

Top	Bot	Thru	Comments
3718	3735		

INVOICED
DATE 2-5-09
INV. NO. 2009061165

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 28 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #2063.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN) CM

Handwritten signature/initials


REPLACEMENT CARD

OIL PRODUCERS, INC. OF KANSAS
 P.O. BOX 8647 WICHITA, KS. 67208 #1 (WHISMAN) ARPIN C E/2 SW NW

4-9-20W

CONTR WOODMAN & IANNITTI OIL CTY ROOKS

GEOL CHUCK IMMICH FIELD ARPIN EAST



ELV 2185 KB SPD 8/9/84 CARD ISSUED 10/11/84 IP OIL WELL
 2181 GL DRLG COMP 8/15/84 ARB OH 3718-3735
 API 15-163-22,457

SMP	Tops	Depth Datum
ANH	1706 + 479	
TOP	3180 - 995	
HEEB	3385 - 1200	
TOR	3407 - 1222	
LANS	3423 - 1238	
BKC	3640 - 1455	
CONG	3697 - 1512	
ARB	3716 - 1531	
PBTD	3734 - 1549	
RTD	3735 - 1550	

8 5/8 " 246 / 140SX, 4 1/2 " 3718 / 100SX
 DST (1) 3584-3603 (LKC) / 30-30-45-60, REC 125' MW, SIP 1225-1225#, FP 31-42 / 42-42#, HP 2004-1951#, BHT 108°
 DST (2) 3693-3735 (CONG, ARB) / 30-30-45-60, REC 320' HMCO (60% OIL, 25% M, 10% G, 5% W), SIP 856-835#, FP 74-84 / 95-127#, HP 2035-2025#
 MICT - CO. (ARB OH), AC 500G (5% MA W/FE) & 1000G (15% HCL W/DOUBLE FE), SWB DWN, SO, SET 2 3/8 " TBG AT 3730.87, POP (POTENTIAL NOT RPTD)

INFO RELEASED: 10.3.85 - WAS OIL WELL - TIGHT HOLE