

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23625-00-01  
Spot: W2E2NWSE Sec/Twnshp/Rge: 7-33S-6E  
2028 feet from S Section Line, 1834 feet from E Section Line  
Lease Name: CHASE Well #: 4  
County: COWLEY Total Vertical Depth: 3120 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 125 N MARKET ST STE 1120  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 4.5   | 3119       | 1114        | 75 SX   |
| SURF   | 8.625 | 308        |             | 175 SX  |

101.40

Well Type: EOR UIC Docket No: E26708.1 Date/Time to Plug: 01/19/2009 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.  
Proposal Rcvd. from: JOE Company: GRESSEL OILFIELD SERVICE, INC. Phone: (620) 463-5161

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/20/2009 12:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 3,010', DUMP BAILED 5 SXS CEMENT ON TOP. TESTED CASING @ 200#, HELD OK. CUT 4 1/2" CASING @ 1,114. LAYED DOWN 18 JOINTS 4-1/2" CASING. WITH CASING @ 360', COPELAND ACID SERVICE ESTABLISHED CIRCULATION & MIXED & PUMPED 150 SXS 60/40 POZMIX 4% GEL TO SURFACE. FINISHED LAYING DOWN 9 JOINTS 4-1/2" CASING. TOPPED WITH OFF WITH CEMENT TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12:30, 1-20-2009.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3084 | 3093 |      |          |

INVOICED

DATE 2-5-09  
INV. NO. 2009061170

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 28 2009

Remarks: COPELAND ACID SERVICE TICKET #33840.

CONSERVATION DIVISION  
WICHITA, KS

Plugged through: CSG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

*PKB*