

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20108-00-01
Spot: NWSW Sec/Twnshp/Rge: 32-30S-18W
1980 feet from S Section Line, 660 feet from W Section Line
Lease Name: SMITH Well #: 1
County: KIOWA Total Vertical Depth: 5190 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 520 S HOLLAND STE 207
WICHITA, KS 67209

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4602		
PROD	4.5	5185	2111	WITH 150 SX CMT 168.68
SURF	8.625	540		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/08/2009 8:00 AM

Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC

Proposal Rcvd. from: EDGAR SANCHEZ Company: ROBERTS RESOURCES Phone: _____

Proposed Plugging Method: PLUG AT 1000' WITH GEL & 50 SX CMT. PLUG AT 570' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 01/08/2009 3:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: LINDLEY REIMER

Actual Plugging Report:

CIBP @ 4602'. PREVIOUS OPERATOR SQUEEZED CASING LEAK AT 2325' WITH 150 SX CMT. TOC @ 2380'. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 570' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5055	5061		


INVOICED
DATE 2-5-09
INV. NO. 2009061172

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 16 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01



Signed _____

[Signature]
(TECHNICIAN)