

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21224-00-01
Spot: NWNE Sec/Twnshp/Rge: 32-30S-18W
4528 feet from S Section Line, 2088 feet from E Section Line
Lease Name: EMERSON-CARAWAY TRUST Well #: 1
County: KIOWA Total Vertical Depth: 5104 feet

Operator License No.: 32781
Op Name: ROBERTS RESOURCES, INC.
Address: 520 S HOLLAND STE 207
WICHITA, KS 67209

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|------------------|
| CIBP | | 4830 | | WITH 2 SX CMT |
| CIBP | | 5000 | | |
| PROD | 4.5 | 5104 | 2822 | WITH 140 SX CMT |
| SURF | 8.625 | 617 | | WITH 1200 SX CMT |

165.88

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/09/2009 9:15 AM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: EDGAR SANCHEZ Company: H2 PLAINS, LLC Phone: (785) 798-3995

Proposed Plugging Method: SET CIBP @ 4830' WITH 2 SX CMT. PLUG AT 1150' WITH 12 SX GEL & 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/07/2009 11:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 4830' WITH 2 SX CMT. 1ST PLUG AT 1150' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 5024 | 5056 | | |

INVOICED


DATE 2-5-09
INV. NO. 2009061172

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 16 2009

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01



Signed

Jerry W. Stapleton
(TECHNICIAN)
PIRT II