

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Cholla Production, LLC
Address: 7851 South Elati Street, Suite 201, Littleton CO, 80120
Phone: (303) 623-4565 Operator License #: 31819
Type of Well: D & A Docket #: none
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11/7/08 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 039-21055-00-00
Lease Name: Bailey
Well Number: 1-5 *S 2 N 2* *KCC Pkt*
Spot Location (QQQQ): S2 - SW - NE - Ne
1180 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 5 Twp. 3 S. R. 26 East West
County: Decatur
Date Well Completed: 11/11/08
Plugging Commenced: 11/13/08 @ 1:30 pm
Plugging Completed: 11/13/08 @ 6:00 pm

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	281	8 5/8	281	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Commenced plugging 11/13/08 @ 1:30 pm, 1st stage: 25sx @ 3863', 2nd: 25sx @ 2155', 3rd: 100sx @ 1450', 4th: 40sx @ 331', 5th: 10sx @ 40', 30sx @ rathole, Total of 230sx of 60/40 poz, - 4% gel, - 1/4# per sx flo-seal, Drilling mud was placed between stages
Plugging was complete 11/13/08 @ 6:00 pm, by SOS Cementing.

Name of Plugging Contractor: WW Drilling, LLC License #: 33575
Address: 233 S 4th, PO Box 307 Wakeeney KS, 67672

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 19 2008


Name of Party Responsible for Plugging Fees: Cholla Production, LLC
State of CO County, ARAPAHOE, ss.

CONSERVATION DIVISION
WICHITA, KS

Emily M. Hundley Giff (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Emily M. Hundley Giff
(Address) 7851 S. Elati St., #201 Littleton, CO 80120

SUBSCRIBED and SWORN TO before me this 16th day of DECEMBER, 20 08
[Signature] My Commission Expires: 4/19/09
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]