

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Richard B. Morris  
Address: P.O. Box 482 Canton Ks 67428-0482  
Phone: (620) 877-7094 Operator License #: 7131  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (IF SWD or ENHR)  
The plugging proposal was approved on: 11/12/08 (Date)  
by: Duane Krueger (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Kansas City Depth to Top: 2018 Bottom: 2083 T.D. 2083  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-015-19741-00-00  
Lease Name: Parris  
Well Number: 1  
Spot Location (Q000): SE SE SW  
330 Feet from  North /  South Section Line  
2310 Feet from  East /  West Section Line  
Sec. 20 Twp. 23 S. R. 4  East  West  
County: Butler  
Date Well Completed: 4/27/48  
Plugging Commenced: 11/14/08  
Plugging Completed: 11/17/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	clay-shells	surface	62'	8 5/8	62'	None
Kansas City	Lime	2018	2083	4 1/2	2046	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom) to (top) for each plug set.  
Ran 2 3/8 to 1917' spotted 50 sacks cement approx 600' pulled 2 3/8 to 253' cut 4 1/2 loose from surface. Ran 249' 1" tubing, circulated cement to surface through 1' approx 100 sacks and through 2 3/8 approx 38 sacks

Name of Plugging Contractor: Sunflower Well service License #: 30280  
Address: P.O. Box 341 Canton, Ks 67428-0341  
Name of Party Responsible for Plugging Fees: Richard B. Morris *Richard B. Morris*  
State of \_\_\_\_\_ County, \_\_\_\_\_ ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) *Richard B. Morris*  
(Address) P.O. Box 482 Canton, Ks 67428-0482


SUBSCRIBED and SWORN TO before me this 12 day of December 2008  
*Thomas L. Kueser* My Commission Expires: 2-3-2012  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 15 2008

CONSERVATION DIVISION  
WICHITA, KS



*PKT*


**WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY** **COPY**  
 412 Union National Bk. Bldg. Wichita, Kansas

Company - **BRANINE & GOERING**  
 Farm - **Parris** No. **1**

SEC. **20** T. **23** **48**  
 SE SE SW

Total Depth. **2083'**  
 Comm. **4-22-48** Comp. **4-27-48**  
 Shot or Treated.  
 Contractor. **Shawver-Graham, Inc.**  
 Issued. **7-3-48**

County. **Butler**  
**KANSAS**



CASING:  
**8-5/8" 62' Cam. 1/40 Sx.**  
**4-1/2" 2046' Cam. 1/50 Sx.**

Elevation. \_\_\_\_\_  
 Production. **Est. 30 Ebls.**

Figures Indicate Bottom of Formations.

clay & shells	40
shale & shells	62
lime & shale	220
lime	280
shale & shells-	840
lime	865
shale & shells	1185
lime	1205
shale	1240
shale & lime	1440
lime	1465
shale & shells	1725
lime	1740
lime & shale	1831
shale & shells	1976
lime & shale	2052
lime, Kansas City	2059
lime	2083
<b>Total Depth</b>	

RECEIVED  
 KANSAS CORPORATION COMMISSION

DEC 15 2008

CONSERVATION DIVISION  
 WICHITA, KS

SUNFLOWER WELL SERVICE, INC.  
 P.O. BOX 341  
 CANTON, KS 67428-0341  
 620-628-4723

INVOICE

TO: RICHARD MORRIS  
 P O Box 482  
 Canton, KS 67428

<u>INVOICE DATE</u>	<u>INVOICE NUMBER</u>	<u>LEASE NAME</u>
11/26/08	1309	Parris #1

<u>DATE</u>	<u>DESCRIPTION</u>	<u>TOTAL</u>
11/14/08	MOVED TO LOCATION:  Rigged up, Ran bailer, Could not get past 900', Ran ripper for weight, Could not get past 900', Went back to yard to load tubing, Shut down.	
	Rig & Crew 5 hrs	\$ 185 per hr \$ 925.00

11/17/08	Ran taper mill and tubing, Worked down to 1087', Pulled mill, Ran 2-3/8" notch collar, Worked and washed down to 1917', Spotted 50 sacks of cement, Pulled tubing to 253', Had to cut 4-1/2" casing loose, Ran 1" tubing to 249', Circulated cement to surface, Pulled 1" tubing and 2" tubing, Rigged down.	
	Rig & Crew 13 hrs	\$185 per hr \$2,405.00
	Power tongs	\$ 50.00
	1" Tubing and tools	100.00
	Pipe dope	15.00

THANK YOU FOR YOUR BUSINESS!!!!

SubTotal	\$3,495.00
Tax 6.3%	220.19
<b>TOTAL</b>	<b>\$3,715.19</b>

TERMS: NET 30 1.5% WILL BE ADDED AFTER 30 DAYS FROM DATE OF SERVICE. PLEASE PAY FROM THIS INVOICE.

RECEIVED  
 KANSAS CORPORATION COMMISSION

DEC 15 2008

CONSERVATION DIVISION  
 WICHITA, KS

*pd 11/29/08*  
*S.P. EK # 5744*  
*\$3715.19*  
*RDM*

# SUNFLOWER WELL SERVICE, INC.

COMPLETION—WORKOVER—ROD & TUBING SERVICE  
408 N. 4TH STREET, P.O. BOX 341, CANTON, KS 67428

1309

Company Richard Morris  
Lease Parris Well # 1  
Unit 3 Oper. B.O Prod. well  New well  Inj. well

DATE	WORK DONE	HRS.	AMOUNT
11-14-08	Moved to location. Rigged up. ran bailer. could not get past 900'. ran ripper for weight could not get past 900'. went back to yard to load tubing. Shut down.		

	Rig crew	5	925.00
11-17-08	Ran taper mill and tubing. work down to 1687'. pulled mill. ran 2 3/8 notch collar. work and wash down to 1917'. Spotted 50 s/lc of gm. pulled tub to 253'. had to cut 1/2 casing loose. Ran 1" tubing to 249'. circulated gm to surface. Pulled 1" tubing and 2" tubing. Rigged down.		
	Rig crew	13	2,405.00

EXTRA EQUIPMENT & SUPPLIES		HRS.	AMOUNT
Power tongs	50 <sup>00</sup>		50.00
Kero. & Paint			
Swab Cups			115.00
Other:	Pipe dope 15 <sup>00</sup> 1" tubing and tool's.		
	100 <sup>00</sup>	SUB TOTAL	3,495.00
		TAX	255.74
			220.19
		TOTAL	3,750.74

WELL RECORD			
Pulled	RODS	Ran	TUBING
	1		3"
	7/8		2 1/2"
	3/4		2
	5/8		subs
	subs		subs
	subs		barrell
	pump		sn
			perf.
			ma

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 15 2008  
CONSERVATION DIVISION  
WICHITA, KS

3715.19



**CONSOLIDATED**  
Oil Well Services, LLC

**REMIT TO**  
Consolidated Oil Well Services, LLC  
Dept. 970  
P.O. Box 4346  
Houston, TX 77210-4346

MAIN OFFICE  
P.O. Box 884  
Chanute, KS 66720  
620/431-9210 • 1-800/467-8676  
FAX 620/431-0012

INVOICE

Invoice # 227618

Invoice Date: 11/24/2008 Terms:

Page 1

MORRIS, RICHARD B  
P.O. BOX 482  
CANTON KS 67428  
( ) -

PARRIS #1  
19630  
11-16-08

Part Number	Description	Qty	Unit Price	Total
1104S	CLASS "A" CEMENT (SALE)	188.00	13.5000	2538.00
1118A	S-5 GEL/ BENTONITE (50#)	800.00	.1700	136.00
1102	CALCIUM CHLORIDE (50#)	200.00	.7500	150.00

Description	Hours	Unit Price	Total
442 MIN. BULK DELIVERY	1.00	315.00	315.00
446 P & A OLD WELL	1.00	625.00	625.00
446 EQUIPMENT MILEAGE (ONE WAY)	20.00	3.65	73.00

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 15 2008

CONSERVATION DIVISION  
WICHITA, KS

*Pd 11/26/08*  
*S.P. CK # 5741*  
*\$ 3986.67*  
*RBM*

Parts:	2824.00	Freight:	.00	Tax:	149.67	AR	3986.67
Labor:	.00	Misc:	.00	Total:	3986.67		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed \_\_\_\_\_ Date \_\_\_\_\_

BARTLESVILLE, OK  
918/338-0808

ELDORADO, KS  
316/322-7022

EUREKA, KS  
620/583-7664

GILLETTE, WY  
307/686-4914

MCALISTER, OK  
918/426-7667

OTTAWA, KS  
785/242-4044

THAYER, KS  
620/839-5269

WORLAND, WY  
307/347-4577



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**ENTERED**

TICKET NUMBER 19630  
LOCATION El Dorado  
FOREMAN Jim Thomas

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
11-16-08	4645	Parris #	20	23	4E	Dodge
CUSTOMER Richard B Morris			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS P.O. Box 482			446	Jacob		
CITY Canton			442	Jacob		
STATE Ks		ZIP CODE 67428				
JOB TYPE Plug	HOLE SIZE	HOLE DEPTH 20832	CASING SIZE & WEIGHT 4 1/2"		OTHER	
CASING DEPTH	DRILL PIPE	TUBING				
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING			
DISPLACEMENT	DISPLACEMENT PSI	MIX-PSI	RATE			

REMARKS: Safety Meeting Rig up + Pump 50 sks class A 3% gel + dis. to 19 1/4"  
Pull up to 253 ft. with 2 3/8" Pump 38 sks class A 4% gel to surface. Run  
1" to 249 ft. Pumped 100 sks class A 4% gel to surface. Cement  
circulated in the cellar. Wash up + rig down.

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405A	1	PUMP CHARGE	62.00	62.00
5406	20	MILEAGE	3.65	73.00
11045	188 sks	class A	13.50	2538.00
1118A	200 lbs	gel	.17	34.00
1102	200 lbs	Calcium chloride	.75	150.00
5407	1	min. Bulk Del.	315.00	315.00
RECEIVED				
KANSAS CORPORATION COMMISSION				
DEC 15 2008				
CONSERVATION DIVISION				
WICHITA, KS				
Subtotal				3970.00
			SALES TAX	193.61
			ESTIMATED	3776.39
			TOTAL	3970.00

Ravin 3737

221618

AUTHORIZATION \_\_\_\_\_

TITLE \_\_\_\_\_

DATE \_\_\_\_\_