

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC

Address: P.O.Box 399 Garden City Ks. 67846

Phone: (620) 275-2963 Operator License #: 4058

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9-23-08 (Date)

by: District 4 (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arb. _____ Depth to Top: 3472 Bottom: 3474 T.D. 3474

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-24645-00-00

Lease Name: Church

Well Number: #1

Spot Location (QQQQ): SW - NE - SE - NW KCC PRT per GRS

3630 Feet from North / South Section Line

2870 Feet from East / West Section Line

Sec. 1 Twp. 17 S. R. 15 East West

County: Barton

Date Well Completed: November 17th 1997

Plugging Commenced: 9-24-08

Plugging Completed: 9-24-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	surface	438	8-5/8	438	none
	Production	surface	3472	5-1/2	3472	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated @ 1490', 900', & 490' ran tbg to 3448' pump 50 sks, cem. w/ 100#s hulls, pull tbg to 2972' pump 14 sks gel, pull tbg to 1500' cir to surface w/ 175 sks, pull tbg, hookup to ann. pump 25 sks cem, SI w/ 250#s, cement was 60/40 poz, 4% gel,

Job complete 1:00 PM

Chase Well Service Inc


Name of Plugging Contractor: Allied Cementing Co. License #: NA RECEIVED KANSAS CORPORATION COMMISSION

Address: P.O.Box 31, Russel Ks, 67665 KCC PRT per CP2/3 6623 **DEC 31 2008**

Name of Party Responsible for Plugging Fees: American Warrior INC CONSERVATION DIVISION WICHITA, KS

State of Kansas County, Finney, ss.

Kevin Wiles SR/ Production Supt. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Handwritten Signature]

(Address) Same

SUBSCRIBED and SWORN TO before me this 30th day of December 20 08

[Handwritten Signature] My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PRT