

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: TriUnited Investors, LLC
Address: 2149 Vizcaya Circle, Campbell, CA. 95008
Phone: (408) 888-1088 Operator License #: 33636
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: October 2, 2008 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3471 Bottom: 3510 T.D. 3510
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-051-23851-00-00
Lease Name: Braun Albert KCCPCT per CPA13
Well Number: 2-1A
Spot Location (QQQQ): _____ - S/2 - S/2 - NE
2938 Feet from North / South Section Line
1302 Feet from East / West Section Line
Sec. 2 Twp. 14 S. R. 17 East West
County: Ellis
Date Well Completed: 4/28/1984
Plugging Commenced: 11/19/2008
Plugging Completed: 11/19/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil	3471'	3510'	8 5/8"	208'	none
				4 1/2"	3507'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 4 1/2" casing @ 1800', 1120', 500', 200'.

Ran tubing to 3300', spot 8 sxs of gel, 40 sxs cement with 200 lbs hulls.

Pulled tubing to 1800' & circulated w/95 sxs cement and 200 lbs hulls. Pulled all tubing and squeezed 4 1/2" csg w/20 sxs cement to 500 psi.

Squeezed 4 1/2" X 8 5/8" annulus with 1 sx cement and 100 lbs hulls to 500 psi. Total of 156 sxs 60/40 Poz mix, 8 sxs gel and 500 lbs hulls.

Name of Plugging Contractor: Super Oil Well Service, Inc. License #: 33930

Address: PO Box 519, Russell, KS. 67665

Name of Party Responsible for Plugging Fees: TriUnited Investors, LLC.

State of California County, Santa Clara, ss.

Terry McCarthy

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roganda Moses


(Address) PO Box 385, Hays, KS. 67601

SUBSCRIBED and SWORN TO before me this 22 day of December, 2008

Brenda S Gabel
Notary Public

My Commission Expires: 3-24-2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas



Handwritten initials