

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: TriUnited Investors, LLC  
Address: 2149 Vizcaya Circle, Campbell, CA. 95008  
Phone: (408) 888-1088 Operator License #: 33636  
Type of Well: Oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: October 2, 2008 (Date)  
by: Case Morris (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3799 Bottom: 3900 T.D. 3900  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 051-22824-00-00  
Lease Name: Kraus A  
Well Number: 6  
Spot Location (QQQQ): nwsuase - SE - NW - NE  
3630/1938 Feet from  North /  South Section Line  
4290/1249 Feet from  East /  West Section Line  
Sec. 26 Twp. 13 S. R. 20  East  West  
County: Ellis  
Date Well Completed: 4/8/1982  
Plugging Commenced: 11/21/2008  
Plugging Completed: 11/21/2008

KCC  
PKT  
per  
GOPS  
  
KCC  
PKT

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil	3799'	3812'	8 5/8"	250'	none
				5 1/2"	3856'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top), for each plug set.

Perforated 5 1/2" casing @ 2100', 1520', 700', 225'.  
Ran tubing to 3600', spot 13 sxs of gel, 50 sxs cement with 200 lbs hulls.  
Pulled tubing to 2100' & circ w/260 sxs cement and 200 lbs hulls. Pulled all tubing.  
Pulled all tubing & squeezed w/30 sxs cement to 500 psi. Tied to 8 5/8" X 5 1/2" annulus and squeezed to 500 psi. Plug down @ 3:00 PM.

Name of Plugging Contractor: Alliance Well Service Inc License #: 33930 34082  
Super Oil Well Service, Inc.  
Address: PO Box 519, Russell, KS. 67665 KCC PKT per CP 213

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: TriUnited Investors, LLC.  
State of California County, Santa Clara, ss.  
Terry McCarthy (Employee of Operator) or (Operator) on above-described well.

DEC 29 2008

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Roger J Moses  
(Address) PO Box 385, Hays, KS. 67601

SUBSCRIBED and SWORN TO before me this 22 day of December, 2008  
Brenda S Gabel My Commission Expires: 3-24-2011  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas

67202  
BRENDA S. GABEL  
State of Kansas  
My Appt. Exp. 3-24-2011

PKT