

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Herman L. Loeb
Address: P.O. Box 524 Lawrenceville, Illinois 62439
Phone: (618) 943-2227 Operator License #: 3273
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: December 22, 2008 (Date)
by: Pat Staab (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Marmaton Depth to Top: 3922 Bottom: 3935 T.D. 4090

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 195-21294 -00-00
Lease Name: Wiesner J
Well Number: 4
Spot Location (QQQQ): NW - SW - SE - SW
380 381 Feet from North / South Section Line
3630 3767 Feet from East / West Section Line
Sec. 3 Twp. 12 S. R. 21 East West
County: Trego
Date Well Completed: Sept. 26, 1983
Plugging Commenced: Dec. 22, 2008
Plugging Completed: Dec. 22, 2008

KCC
PST
CAPS

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0	1022	8 5/8"		None
	Production	0	4090	5 1/2"		None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP @ 3400' Dumped two sacks of cement on plug. Ran in with a perforating gun and perforated at 970' with 2 shots.
Ran tubing to 2275' and circulated 180 sacks of 60/40 poz w/4% gel and 200 lbs of hulls to surface. Pulled the tubing and filled the 5 1/2" casing with 20 sacks of cement. Hooked onto the backside and pumped 20 sacks of cement down the 8 5/8" at 300 lbs pressure, shut the casing in. Plug down at 12:30 PM Allied Cementing Co. LLC

Name of Plugging Contractor: Alliance Well Service License #: 35346 RECEIVED
Address: Pratt, Kansas KCC 34082 DEC 30 2008
Name of Party Responsible for Plugging Fees: Herman L. Loeb CONSERVATION DIVISION
State of Illinois County, Lawrence, ss. WICHITA, KS

Roland Nyp (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Roland Nyp
(Address) 804 Main Stockton, Kansas 67669

SUBSCRIBED and SWORN TO before me this 29th day of December, 2008
Irene R Nyp My Commission Expires: September 30, 2012
Notary Public

PST