

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20873-00-00  
Spot: NWSENW Sec/Twnshp/Rge: 8-30S-39W  
*KCC MET SR*  
*PLUG PS*  
3540 feet from S Section Line, 3480 feet from E Section Line  
Lease Name: JAY MORRIS Well #: 1-8  
County: STANTON Total Vertical Depth: 5974 feet

Operator License No.: 32309  
Op Name: PRESCO WESTERN LLC  
Address: 5665 FLATIRON PKWY  
BOULDER, CO 80301

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| CIBP   |       | 3000       |             |                 |
| CIBP   |       | 5493       |             | WITH 2 SX CMT   |
| DVT    |       | 2939       |             |                 |
| PROD   | 4.5   | 5973       | 0           |                 |
| SURF   | 8.625 | 1825       |             | WITH 670 SX CMT |

*194.16*

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/03/2008 2:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: STEVE RIDENHOUR Company: PRESCO WESTERN Phone: (303) 444-8881

Proposed Plugging Method: CIBP @ 5493' WITH 2 SX CMT. CIBP @ 3000'. PLUG AT 2968' WITH 25 SX CMT. PLUG AT 1857' WITH 40 SX CMT. PLUG AT 600' WITH 40 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/04/2008 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAKS @ 3831-4110'. CIBP @ 5493' WITH 2 SX CMT. CIBP @ 3000'. 1ST PLUG AT 2968' WITH 25 SX CMT. 2ND PLUG AT 1857' WITH 40 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT IN 2 STAGES. 4TH PLUG PUMP 15 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURE TO 300#.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 5666 | 5672 |      |          |
| 5656 | 5664 |      |          |
| 5644 | 5652 |      |          |

INVOICED  
DATE 1-21-09  
INV. NO. 2009061050

RECEIVED  
KANSAS CORPORATION COMMISSION


DEC 24 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01



Signed

*Ken Jehlik*

(TECHNICIAN)

*PKT*