

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20118-00-00
Spot: NENENW Sec/Twnshp/Rge: 3-3S-14E
4979 feet from S Section Line, 2686 feet from E Section Line
Lease Name: EPPL E B Well #: 2
County: NEMAHA Total Vertical Depth: 3927 feet

Operator License No.: 6101
Op Name: TEICHGRAEBER OIL, INC.
Address: 700 N MAIN ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3925		200 SX
SURF	8.625	251		175 SX

127.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2008 8:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: RICK STOUT Company: TEICHGRAEBER OIL, INC. Phone: (620) 583-2173

Proposed Plugging Method: AS RECOMMENDED BY KCC, PROPOSE 20 SACKS PLUG ABOVE PERFORATIONS, CEMENT FROM 310 TO SURFACE.

Plugging Proposal Received By: RUSSELL HINE Witness Type: NONE
Date/Time Plugging Completed: 03/14/2008 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

PUMPED 20 SACKS OF CEMENT AT 3601'. PERFORATED THE 5 1/2" CASING AT 1350' AND 170'. PUMPED 20 SACKS OF CEMENT AT 1350'. PULLED THE TUBING UP TO 350' AND CIRCULATED 90 SACKS OF CEMENT ON THE INSIDE AND OUTSIDE OF THE 5 1/2" CASING TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3867	3869		
3839	3841		
3616	3617		

RECEIVED
KCC DISTRICT #3

DEC 10 2008 TCH

CHANUTE, KS

INVOICED
DATE 1-22-09
INV. NO. 2009061062

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 22 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)