

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-131-20126-00-00  
Spot: SESESW Sec/Twnshp/Rge: 34-2S-14E  
344 feet from S Section Line, 2831 feet from E Section Line  
Lease Name: EPPLE/SCHUMANN Well #: 1  
County: NEMAHA Total Vertical Depth: 3666 feet

Operator License No.: 6101  
Op Name: TEICHGRAEBER OIL, INC.  
Address: 700 N MAIN ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3662		200 SX
SURF	8.625	263		130 SX

119.15

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2008 8:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: RICK STOUT Company: TEICHGRAEBER OIL, INC. Phone: (620) 583-2173

Proposed Plugging Method: AS RECOMMENDED BY KCC, 20 SACKS @ BOTTOM ABOVE PERFORATIONS, TOP PLUG FROM 310 TO SURFACE.

Plugging Proposal Received By: LARRY MARCHANT Witness Type: NONE  
Date/Time Plugging Completed: 03/11/2008 5:00 PM KCC Agent: TAYLOR HERMAN

**Actual Plugging Report:**

PUMPED 20 SACKS OF CEMENT AT 3646'. PULLED THE TUBING UP TO 1350' AND PUMPED 20 SACKS OF CEMENT. PULLED THE TUBING UP TO 350' AND CIRCULATED 50 SACKS OF CEMENT TO SURFACE INSIDE AND OUTSIDE OF THE 5 1/2" CASING.

**Perfs:**

Top	Bot	Thru	Comments
3602	3614		

INVOICED

DATE 1-22-09

INV. NO. 2009061062

RECEIVED  
KANSAS CORPORATION COMMISSION  
**DEC 22 2008**  
CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
KCC DISTRICT #3

DEC 10 2008

CHANUTE, KS

TCH

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

PST