

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-187-20191-00-00

*Per GPS*  
*1-22-09*  
*CPB*

Spot: ~~NENESESW~~ *NWSE* Sec/Twnshp/Rge: 6-30S-39W

*1286* 1250 feet from S Section Line, *2360* 2350 feet from E Section Line

Lease Name: BAUGHMAN GU E

Well #: 2

County: STANTON

Total Vertical Depth: 2771 feet

Operator License No.: 5952

Op Name: BP AMERICA PRODUCTION COMPANY

Address: 2225 W OKLAHOMA AVE  
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1490		
PROD	5.5	2771	0	WITH 800 SX CMT <i>90.06</i>
SURF	8.625	608		WITH 400 SX CMT

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 12/10/2008 10:00 AM

Plug Co. License No.: 99997

Plug Co. Name: HALLIBURTON ENERGY SERVICES

Proposal Rcvd. from: KEVIN STRUBE

Company: BP AMERICA

Phone: (620) 356-1237

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: NONE

Date/Time Plugging Completed: 12/10/2008 1:00 PM

KCC Agent: STEVE DURRANT

Actual Plugging Report:

4" CASING PATCH @ 1530-1653'. CIBP @ 1490'. TOP OF STUCK TBG @ 1535'. TOP OF STUCK RODS @ 1515'. RAN TBG TO 1477' & CIRCULATE CMT TO SURFACE IN 2 STAGES USING 125 SX CMT. PUMP 50 SX CMT DOWN ANULUS TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
2577	2692		


**INVOICED**  
DATE 1-15-09  
INV. NO. 2009061010

RECEIVED  
KANSAS CORPORATION COMMISSION  
**DEC 19 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: TBG

District: 01



Signed

*Steve Durrant*

(TECHNICIAN)

*PKT*