

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00426-00-01
Spot: S2S2SW Sec/Twnshp/Rge: 8-11S-16W
330 feet from S Section Line, 3960 feet from E Section Line
Lease Name: ZIEGLER Well #: 1
County: ELLIS Total Vertical Depth: 3375 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3372	0	w/unknown sxs cmt
SURF	8.625	1017	0	w/unknown sxs cmt <u>109.69</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2008 12:00 PM
Plug Co. License No.: 32247 Plug Co. Name: CRAWFORD, JEFF DBA JEFF'S OILWELL SUPERVISION
Proposal Rcvd. from: JERRY GREEN Company: CASTLE RESOURCES, INC. Phone: (785) 625-5155

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls.
OWWO well. Out of hole at 1660'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2008 5:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1647' - pumped 110 sxs cement with 200# hulls.
Pulled tubing out - tied onto 4 1/2" - pumped 15 sxs cement.
Max. P.S.I. 500#. Shut in - full.
Tied onto 8 5/8" - pressured to Max. P.S.I. 1000#. Shut in - full.

Perfs:

INVOICED
DATE 1-15-09
INV. NO. 2009061012


RECEIVED
KANSAS CORPORATION COMMISSION
DEC 16 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: WELL ORIGINALLY KNOWN AS EUNICE-LIEB #1. ALLIED CEMENTING COMPANY-TICKET #35102.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

DEC 12 2008

PKT

FRONTIER OIL

#1 EUNICE-LIEB

8-11-16W
C S2 S2 SW

Contr. STRATA DRILLING

ELLIS

County

E 1812 RB Comm. Comp. 9-28-56 IP 83 BOPD/ARB

Tops	Depth	Datum
ANH	1007	805
HEEB	2961	-1149
TOR	2984	-1172
LANS	3005	-1193
B/KC	3248	-1436
CONG	3290	-1478
SIMP	3318	-1506
SIMP DOL	3337	-1525
ARB	3370	-1558
TD	3375	-1563

Casing
 8" 1017
 4" 3372

DST 3038-70/2 HRS, 350' G, 150'
 H GC, SL OCM, BHP 900#

DST 3371-75/2 HRS, 2501' FRE O,
 1020#

SWB 22 BOPH/4 HRS: CO 3375, 23
 BOPH/4 HRS, NAT, NW

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

