

6 030991

10-29-87 KCC 6 15-179-20389-00-01

STATE CORPORATION COMMISSION
REGISTRATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SW, SEC. 15, T 10 S, R 30 W E
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6033

Lease Name Dickman Well # 1-15

Operator: Murfin Drilling Co.

County Sheridan 139.43

Name & Address 250 North Water Suite 300
Wichita, Kansas 67202

Well Total Depth 4290 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated OWWO

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Kansas

Company to plug at: Hour: _____ AM Day: 29 Month: October Year: 19 87

Plugging proposal received from Ronnie

(company name) Kelso (phone) _____

were: 8 5/8" set at 284' cwc 4 1/2 set at 4280'. PBD 4237 Perf. 4179' - 83'

4214' - 18'. Order sand and Common cement. Pull pipe. Order 200 sks Econolite

65/35 Pozmix 10% Gel 2% Dicl. Halliburton Cement Blend 5 sks Hulls. Newman Water

Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:00 AM Day: 29 Month: Oct. Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 4120' w/4 sks Common Cement on sand w/bailer.

4 shots 2500' 2000' 1800' 1400'. Recovered 1400' of casing. Squeezed 8 5/8

w/200 sks cement blend w/ 4 sks Hulls. Max Psi 300#. Close in Psi 200#. Plug

complete.

RECEIVED
STATE CORPORATION COMMISSION

NOV 18 1987

Remarks: _____

(If additional description is necessary, use BACK of this report.)

(If applicable, observe this plugging.)

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INVOICED
DATE 12-3-87
INV. NO. 19054