

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-15562-00-00  
Spot: SWNENE Sec/Twnshp/Rge: 21-20S-12W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: GELWICKS Well #: 7  
County: BARTON Total Vertical Depth: 3422 feet

Operator License No.: 3942  
Op Name: MONROE, ORVILLE DBA BIG "O"  
Address: 2820 PASEO DR  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3262		
PROD	5.5	3396	0	125 SX
SURF	8.625	267	0	250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/30/2008 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 793-2134

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Perfed at 1550' - 600' - 250'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/30/2008 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 1600' - pumped 100 sxs cement with no hulls.  
Pumped 160 sxs cement with 300# hulls - circulated to surface.  
Pulled tubing - topped off with 40 sxs cement.  
Max. P.S.I. 125#. Cement circulated out backside to surface.

Perfs:

Top	Bot	Thru	Comments
3218	3222		
3208	3210		
3188	3191		
3149	3152		
0	0		

INVOICE  
DATE 1-23-09  
INV. NO. 2009061064

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 07 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.  
Plugged through: CSG

District: 04 Signed Bruce Rodie  
(TECHNICIAN) CM

JAN 02 2009

PT

21-20-12W 53

SW NE NE

CHARLES HULME

#7

GELWICKS

Contr. CHARLES HULME

BARTON

County

E 1829 Comm. 11-18-57 Comp. 1-10-58 IP 79 BOPD/ARB

PHY POT

Tops	Depth	Datum
HEEB	3010	-1181
LANS	3150	-1321
CONG	3385	-1556
ARB	3395	-1566
TD	3422	-1593

Casing

8" 267

5" 3396

DP: ACID 500: SWB 90 B0/12

HRS

WORKMAN NW POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS