

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20420-00-00
Spot: NWNENE Sec/Twnshp/Rge: 33-4S-22W
150 feet from N Section Line, 990 feet from E Section Line
Lease Name: VANDIEST Well #: 1
County: NORTON Total Vertical Depth: 3725 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
MSSC		1872		
PROD	5.5	3724	0	575 SX
SURF	8.625	219	0	150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2008 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 4% gel - 400# hulls - 12 sxs gel spacer.
CIPB at 3680'.
Port collar at 1872' w/400 sxs cwc.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2008 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Quality Oilwell Cementing pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls, followed with 12 sxs gel spacer, followed with 185 sxs 60/40 pozmix - 4% gel with 200# hulls.
Max. P.S.I. 900#. S.I.P. 700#.
Hooked up to backside and pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3721	3723		SPF
3680			BRIDGE PLUG
3630	3632		SPF
3610	3612		SPF
3598	3600		SPF

INVOICED
DATE 1-23-09
INV. NO. 2009061065

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 02 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 04

Signed

Richard Williams
(TECHNICIAN)

CM

act

BLACK DIAMOND OIL
HAYS KS 67601-0641

WILDCAT

33-04S-22W
180' N, C NW NE NE

#1 VANDIEST

site: 1-1/2 N & 3 W OF DENSMORE KS	city: NORTON	API: 15-137-20420
contr: DISCOVERY DRILLING #1	field: WC (HANSEN ESTATE WEST	
opd: KENNETH VEHIGE	DISC)	
fr date: 07/18/2003	spd date: 08/25/2003	orig comp: 08/30/2003
	card issued: 03/01/2004	last revised: 03/22/2004

ELV: 2281 KB, 2273 GL LOG
tops.....depth/datum
ANH.....1912 +369
TOP.....3226 -945
HEEB.....3423 -1142
TOR.....3448 -1167
LANS.....3468 -1187
LANS C.....3515 -1234
BKC.....3650 -1369
PBD.....3680 -1399
GORHAM SD.....3700 -1419
B/GORHAM SD.....3716 -1435
ARB.....3721 -1440
LTD.....3725 -1444
RTD.....3725 -1444

IP status:
OIL, P 15 BO & 80 BWPD, LKC 3598-3632 OA, 12/15/2003
NOTE: INFO RELEASED 3/22/2004 - ADDED DSTS
CSG: 8-5/8" 219.50 / 150 SX (ALT 2), 5-1/2" 3724 / 175 SX,
PORT COLLAR AT 1872 / 400 SX
NO CORES
DST (1) 3419-3477 (TOR), / 45-45-45-45, (1ST OP) FB BLT TO
4.5 INCH IN. BKT, ISI: NO BLO BK, (2ND OP) WK SURF
BLO/20", FS: NO BLO BK, REC 85' M, NS, REMARK: ALL
PRESSURES ARE ALPINE READINGS ISIP 1211# FSP
1191# IFP 48# -57# FFP 60# -69# IHP 1630# FHP 1569# BHT
100'

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA KANSAS

(over)

BLACK DIAMOND OIL
HAYS KS 67601-0641

33-04S-22W
180' N, C NW NE NE

#1 VANDIEST

DST (2) 3482-3520 (LANS C), / 40-60-10-0, (1ST OP) WB BLT TO 3.5 INCH IN BKT, FLUSH TOOL, SURGED, (2ND OP) NB, TOOH, REC 50' OIL SPKD M, REMARK: ALL PRESSURES ARE ALPINE READINGS ISIP 1195# IFP 50# -54# FFP 54# -55# IHP 1691# FHP 1614# BHT 98'

DST (3) 3585-3655 (LANS JL), / 45-45-30-30, (1ST OP) GB OFF BTM BKT/10", ISI: BLO BK/4" & BLT TO 3 INCH IN BKT, (2ND OP) GB OFF BTM BKT/6", 630' GIP, REC 945' TF: 105' GSY OIL (5% G, 95% OIL, GR 36), 150' MCO (85% OIL, 15% M), 60' HMCO (10% G, 65% OIL, 25% M), REMARK: ALL PRESSURES ARE ALPINE READINGS ISIP 1129# FSP 1120# IFP 39# -107# FFP 115# -148# IHP 1761# FHP 1729# BHT 105'

DST (4) 3704-3720 (GORHAM SD), / 30-45-0-0, (1ST OP) WK SURF BLO, ISI: NO BLO BK, (2ND OP) NB, TOOH, REC 3' M, NS, REMARK: ALL PRESSURES ARE ALPINE READINGS ISIP 31# IFP 27# -30# IHP 1836# FHP 1772# BHT 99'

TRGT ZN: ARB (OIL), PTD 3750 (ARB), MICT - CO, PF (ARB) 3721-3723, W / 4 SPF, AC 250 GAL (MCA), SWB LD, NON-COMMERCIAL, SET CIBP AT 3680, PF (LKC) 3598-3600, 3610-3612, 3630-3632, W / 1 SPF, AC 1500 GAL (MCA), SWB LD, SO, SET 2-7/8" TBG AT 3665, NO PKR, POP, IPP 15 BO & 80 BWPD, 12/15/2003