

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20661-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 26-8S-19W  
4290 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: VEVERKA Well #: 4  
County: ROOKS Total Vertical Depth: 3425 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3417	0	150 SX + 400
SURF	8.625	198	0	150 SX <u>111.31</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/31/2008 9:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 4% gel - 300# hulls - 4 sxs c.c. on side.  
05/11/2006 - squeezed 1995'- 2281' with 250 sxs.  
DV Tool at 1386' w/400 sxs.  
Casing collapsed at 1750'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/31/2008 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1725' - tagged bottom.  
Pulled to 1697' - pumped 50 sxs 60/40 pozmix - 4% gel neat - followed with 50 sxs 60/40 pozmix - 4% gel with 5% c.c. and 100# hulls.  
Pulled tubing out - shut in two hours.  
Ran tubing to 1150' - tagged cement.  
Quality pumped 70 sxs 60/40 pozmix - 4% gel with 150# hulls - circulated cement.  
PTOH. Topped off with 15 sxs - casing full.  
Hooked up to backside - pumped 5 sxs.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3417	3425	OH	
3413	3419		
3402	3410		
3326	3330		
3222			
3217			
3200			

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 07 2009  
CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 1-23-09  
INV. NO. 2009061065

Remarks: QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

JAN 05 2009

PKT

