

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23427-00-00
Spot: SWNENE Sec/Twnshp/Rge: 34-8S-25W
1120 feet from N Section Line, 880 feet from E Section Line
Lease Name: TOLL-08 Well #: 1
County: GRAHAM Total Vertical Depth: 4090 feet

Operator License No.: 33629
Op Name: GREAT PLAINS ENERGY, INC.
Address: PO BOX 292
WAHOO, NE 68066

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4090	193	w/150 sxs cmt
SURF	8.625	208	0	w/unknown sxs cmt 132.93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/02/2009 9:00 AM
Plug Co. License No.: 34066 Plug Co. Name: TRINITY OILFIELD SERVICES INC.
Proposal Rcvd. from: HAROLD BELLERIVE Company: X-HAND ENGINEERING, INC. Phone: (785) 635-4531

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 400# hulls.
Port collar at 2205'.
CIBP at 3750' w/4 sxs - cement on top.
Perforated at 1400' - 2200'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/02/2009 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2200' - pumped 65 sxs 60/40 pozmix - 4% gel with 125# hulls.
Pulled tubing to 1220' - pumped 170 sxs 60/40 pozmix - 4% gel with 125# hulls - circulated to surface.
Pulled all tubing and 193' of 4 1/2" casing - pumped 5 sxs 60/40 pozmix - 4% gel to top off.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 07 2009
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 1-23-09
INV. NO. 2009061070

Remarks: ALLIED CEMENTING COMPANY-TICKET #33354.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

JAN 05 2009

Pat