

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-24705-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 26-26S-13E
386 feet from S Section Line, 2985 feet from W Section Line
Lease Name: PRUE Well #: 2
County: WOODSON Total Vertical Depth: 1520 feet

Operator License No.: 33474
Op Name: ARMADILLA OIL & GAS, LLC
Address: 2045 340TH ST
MADISON, KS 66860

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1520	0	
SURF	4	42		

49.40

Well Type: OG UIC Docket No: Date/Time to Plug: 10/07/2008 8:00 AM
Plug Co. License No.: 5684 Plug Co. Name: SAGE, LARRY GEORGE
Proposal Rcvd. from: GEORGE SAGE Company: SAGE, LARRY GEORGE Phone: (620) 437-6009

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 1520' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 750', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 275' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 10/07/2008 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

2" TUBING WAS RAN INTO THE 4 1/2" CASING TO 1430'. 5 SACKS OF CEMENT WERE PUMPED THROUGH THE 2" TUBING TO 1430'. THE TUBING WAS PULLED TO 750' AND 5 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 275'. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. THE 2" TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

DEC 10 2008

CHANUTE, KS

CPT
by BH

INVOICED
DATE 1-15-09
INV. NO. 2009060983

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 15 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: SPOT LOCATION ESTABLISHED VIA NAD 83 AS386' NSL & 2985' WEL

Plugged through: TBG

District: 03

Signed

Clayton Titel by BH
(TECHNICIAN)

PCY