

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20543-00-00
Spot: SESW Sec/Twnshp/Rge: 13-23S-22W
660 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KROPP Well #: 2
County: HODGEMAN Total Vertical Depth: 4394 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W 93 N PO BOX 360
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4394	940	WITH 300 SX CMT
SURF	8.625	361		WITH 225 SX CMT <u>142.81</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2008 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: SAND TO 4280' & 5 SX CMT. PLUG AT 1400' WITH 50 SX CMT. PLUG AT 650' WITH 80 SX CMT. PLUG AT 390' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2008 5:10 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4230' & 4 SX CMT. SHOT CSG AT 1040'. WOULD NOT COME LOOSE. SHOT CSG @ 940'. 1ST PLUG AT 900' WITH 40 SX CMT. 2ND PLUG AT 620' WITH 50 SX CMT. 3RD PLUG AT 360' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4330	4340		


INVOICED
DATE 1-15-09
INV. NO. 2009060987

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 15 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed Michael Maier
(TECHNICIAN)