

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20660-00-00
Spot: NENESWNE Sec/Twnshp/Rge: 28-18S-31W
1376 feet from N Section Line, 1376 feet from E Section Line
Lease Name: MILDRED STRODE Well #: 1A
County: SCOTT Total Vertical Depth: 2952 feet

Operator License No.: 32356
Op Name: INTERMOUNTAIN REFINING CO, INC
Address: PO BOX 35
FARMINGTON, NM 87499

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2927	0	WITH 285 SX CMT
SURF	7	363		WITH 175 SX CMT <u>95.94</u>

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/21/2008 1:00 PM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: PUMP 500# HULLS & FILL WITH CMT. BRING 50 SX CMT TO PUMP DOWN BACKSIDE.

Plugging Proposal Received By: LINDLEY REIMER
Date/Time Plugging Completed: 11/21/2008 2:30 PM

WitnessType: COMPLETE (100%)
KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING FROM 2762' TO 0' USING 150# HULLS, 25 BALL SEALERS, & 165 SX CMT. PRESSURE TO 1000 PSI. HELD AT 400 PSI. HOOK TO ANNULUS AND PUMP 15 SX CMT. PRESSURE TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
2751	2762		2 SHOTS PER FOO

INVOICED

DATE 1-15-09

INV. NO. 2009060992

RECEIVED
KANSAS CORPORATION COMMISSION


DEC 15 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01



Signed

[Handwritten Signature]

(TECHNICIAN)

Form CP-2/3

[Handwritten initials]