

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23754-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 31-6S-17W
2300 feet from N Section Line, 1970 feet from W Section Line
Lease Name: LEONARD MUIR Well #: 1-31
County: ROOKS Total Vertical Depth: 3470 feet

Operator License No.: 9810

Op Name: MCELVAIN, OIL & GAS PROPERTIES, IAC

Address: 1050 17TH ST STE 1800
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	264		w/180 sxs cmt

112.78

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/28/2008 1:00 AM

Plug Co. License No.: 33493

Plug Co. Name: AMERICAN EAGLE DRILLING LLC

Proposal Rcvd. from: ANDY DINKEL

Company: MCELVAIN, OIL & GAS PROPERTI Phone: (303) 893-0933

Proposed Plugging Method: Ordered 245 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER

WitnessType: NONE

Date/Time Plugging Completed: 11/28/2008 3:30 AM

KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 3402' w/25 sxs.
2nd. Plug at 1375' w/25 sxs.
3rd. Plug at 870' w/100 sxs.
4th. Plug at 300' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

INVOICED
DATE 1-15-09
INV. NO. 2009060996

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 11 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Ed Schumacher
(TECHNICIAN)

CM

Form CP-2/3

DEC 04 2008

PKT