

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23933-00-01
Spot: NESWSWSE Sec/Twnshp/Rge: 19-19S-21W
425 feet from S Section Line, 2215 feet from E Section Line
Lease Name: GNEICH P Well #: 1 TWIN
County: NESS Total Vertical Depth: 4405 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1474		CMT TO SURFACE
PROD	5.5	4383	0	WITH 125 SX CMT 143.16
SURF	8.625	316		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/16/2008 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BENNIE DILLS Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed Plugging Method: RUN TBG TO BOTTOM & PUMP CMT & HULLS. PUL TBG TO ANHYDRITE & CIRCULATE CMT. PULL TBG & TOP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2008 6:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4300' & PUMP 50 SX CMT & 200# HULLS. PULL TBG TO 1495' & PUMP 175 SX CMT. PULL TBG & TOP OFF WITH 20 SX CMT. BACKSIDE HEAD WAS FULL OF CMT AT BOTH BULL PLUGS.

Perfs:

Top	Bot	Thru	Comments
4383	4405		MISSISSIPPIAN OS
4381	4383		OH


INVOICED
DATE 1-15-09
INV. NO. 2009061000

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 15 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

Form 0226 PKT