

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-21073-00-00
Spot: NWNESWSE Sec/Twnshp/Rge: 9-3S-41W
1025 feet from S Section Line, 1829 feet from E Section Line
Lease Name: WALTER,R Well #: 34-09
County: CHEYENNE Total Vertical Depth: 1495 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2101 CEDAR SPRGS RD, STE 1500
DALLAS, TX 75201

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.62	274		

48.59

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/13/2008 7:00 AM
Plug Co. License No.: 33532 Plug Co. Name: ADVANCED DRILLING TECHNOLOGIES LLC
Proposal Rcvd. from: CRAIG Company: ROSEWOOD RESOURCES, INC. Phone: (214) 849-9300

Proposed Plugging Method: Ordered 175 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.
18 joints drill pipe and bit stuck in the hole at 1405'.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 11/13/2008 9:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 1405' w/100 sxs.
2nd. Plug at 324' w/40 sxs.
3rd. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

INVOICED
DATE 1-15-09
INV. NO. 2009061001

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 11 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: LONGHORN CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)

CM

PKT

Form CP-2/3

DEC 04 2008