

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24872-00-00
Spot: NWNESEW Sec/Twnshp/Rge: 4-19S-22W
2436 feet from S Section Line, 2013 feet from W Section Line
Lease Name: BK Well #: 1-4
County: NESS Total Vertical Depth: 4500 feet

Operator License No.: 31514
Op Name: THOROUGHBRED ASSOCIATES L.L.C.
Address: 8100 E 22ND ST STE 600
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	258		WITH 165 SX CMT

146.25

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/30/2008 7:30 AM

Plug Co. License No.: 5147 Plug Co. Name: BEREDCO, INC.

Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 11/30/2008 9:30 AM

WitnessType: NONE
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs: _____


INVOICED
DATE 1-15-09
INV. NO. 2009061003

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 15 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Michael Maier

(TECHNICIAN)