

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05901-00-00
Spot: NWNE Sec/Twnshp/Rge: 26-11S-17W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: MCCORD Well #: 3
County: ELLIS Total Vertical Depth: 3548 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3523	0	w/unknown sxs cmt
SURF	8.625	1085	0	w/unknown sxs cmt <u>115.31</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2008 11:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 885-8240

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel spacer.
Perforated at 750' and 150'.
Squeezes at 1133' - 2175' & 2195' w/100 sxs; 2201' - 2265' w/150 sxs; 2370' - 2400' w/100 sxs; 2839' - 2871' w/100 sxs.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2008 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3007' - pumped 13 sxs gel spacer followed with 60 sxs 60/40 pozmix - 4% gel and 100# hulls.
Pulled tubing to 1100' - pumped 125 sxs 60/40 pozmix - 4% gel and 300# hulls - circulated to surface.
Pulled all tubing - pumped 25 sxs 60/40 pozmix - 4% gel to fill 5 1/2" casing - circulated 8 5/8" to surface.
S.I.P. 175#.

Perfs:

INVOICED
DATE 1-15-09
INV. NO. 2009061005

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 11 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM PKT

CITIES-SERVICE OIL CO

#3 McCORD

26-11-17W
NW NE NE

Contr.

ELLIS County

E 2057 Comm. 4-30-40 Comp. 5-21-40 IP


3000 BOPD

ECHO

Tops	Depth	Datum
ARB	3521	
TD	3528 or 3548	

Casing
8" 1085
5" 3523

A/1000



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS