

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCC Agent Bedore
1619 1740*

API Well Number: 15-051-05906-00-00

Spot: SEWSE

Sec/Twnshp/Rge: 26-11S-17W

1619 1740 feet from S Section Line,

1650 feet from E Section Line

Lease Name: MCCORD A

1738 Well #: 8

County: ELLIS

Total Vertical Depth: 3562 feet

Operator License No.: 5030

Op Name: VESS OIL CORPORATION

Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3555	0	w/unknown sxs cmt
SURF	8.625	1109	0	w/unknown sxs cmt

115.77

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/03/2008 12:00 PM

Plug Co. License No.: 32452

Plug Co. Name: SMOKY HILLS WELL SERVICE

Proposal Rcvd. from: JOEL STULL

Company: VESS OIL CORPORATION

Phone: (785) 885-8240

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls - 12 sxs gel spacer.
Perforated at 1650' - 1110' - 750' - 150'.
Submersible pump stuck in the hole at 3100'.

Plugging Proposal Received By: PAT BEDORE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/03/2008 2:00 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Ran tubing to 3007' - pumped 7 sxs gel spacer followed with 60 sxs 60/40 pozmix - 4% gel and 100# hulls.
Pulled tubing to 1676' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls - circulated to surface.
Pulled all tubing - pumped 45 sxs 60/40 pozmix - 4% gel to fill 5 1/2" casing - circulated 8 5/8" to surface.
S.I.P. 200#.

INVOICED
DATE 1-15-09
INV. NO. 2009061005

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 11 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #34817.

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

PVT

CITIES SERVICE OIL CO

#A-8 McCORD

26-11-17W

SE NW SE

Contr.

ELLIS County

E 2093

Comm. 3-2-41

Comp. 4-16-41

IP

3000 BOPD

ECHO

Tops	Depth	Datum
ARB	3552	
TD	3562	

Casing

8" 1109

5" 3555

1820' OIH @ 3562

A/500

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

12/9/2008