

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-19570-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 33-30S-16E  
400 feet from N Section Line, 420 feet from W Section Line  
Lease Name: UNIT 1-CRAMER Well #: CRAMER 1  
County: WILSON Total Vertical Depth: 840 feet

Operator License No.: 3830  
Op Name: A X & P, INC.  
Address: PO BOX 1176  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.125	800		
SURF	12	30		

35

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/10/2008 8:00 AM  
Plug Co. License No.: 3830 Plug Co. Name: A X & P, INC.  
Proposal Rcvd. from: JURGEN J. HANKE Company: A X & P, INC. Phone: (620) 325-5212

Proposed Plugging Method: Remove pipe string from well, perforate at selected intervals, and then fill from btm to top thru cement string.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 06/05/2008 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

780' of the 2" pipe were removed. The well was then perforated at 550', 175' and 40'. A 1" cement string was lowered to 750' and a 50' cement plug spotted. The cement string was raised to 500' and a 50' cement plug spotted. The cement string was raised to 250' and the well filled to surface with cement. Gel spacers were used between cement plugs. A total of 100 sacks of portland cement were used to plug well.

Perfs:

**INVOICED**  
DATE 1-21-09  
INV. NO. 2009061035

RECEIVED  
KCC DISTRICT #3

DEC 15 2008 AD

CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 22 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)

PKT