

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-19572-00-00

Spot: NWNWNW

Sec/Twnshp/Rge: 32-30S-16E

10 feet from N Section Line,

640 feet from W Section Line

Lease Name: UNIT A-CRAMER

Well #: CRAMER 37 T

County: WILSON

Total Vertical Depth: 809 feet

Operator License No.: 3830

Op Name: A X & P, INC.

Address: PO BOX 1176

INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2	785		
SURF	10	32		

35

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 05/15/2008 8:00 AM

Plug Co. License No.: 3830

Plug Co. Name: A X & P, INC.

Proposal Rcvd. from: JURGEN J. HANKE

Company: AX & P, INC.

Phone: (620) 325-5212

Proposed  
Plugging  
Method:

Run cement string to TD and fill from btm to top.

Plugging Proposal Received By: TAYLOR HERMAN

Witness Type: NONE

Date/Time Plugging Completed: 06/05/2008 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1" cement string was lowered down the inside of 2" pipe to 750' and 5 sacks of cement spotted. A 1" cement string was lowered down the outside of the 2" pipe and cement was tagged at 560'. The 2" pipe was then perforated at 500'. A 1" cement string was lowered to 550' and cement circulated inside and outside the 2" pipe to surface. A total of 185 sacks of portland cement were used to plug well.

INVOICED

DATE 1-21-09

INV. NO. 2009061035

RECEIVED  
KCC DISTRICT #3

DEC 15 2008

AMB

CHANUTE, KS

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 22 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 03

Signed

Alan M. Dunning  
(TECHNICIAN)

PKY