

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

This well was drilled in 1963  
API NUMBER 15-205-19668-00-00  
SE SE NW Sec/Twp/Rge Sec 29 T30S R16E  
2700 feet from south section line  
3200 feet from east section line **35**

TECHNICIAN'S PLUGGING REPORT

Operator License # 3830  
Operator: A X & P, Inc.  
Name & P O Box 1176  
Address Independence, Kansas 67301  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Unit 1 - Ellis #32L  
County Wilson  
Well Total Depth 800 feet  
Production Pipe: 2 Size Feet 775  
Surface Casing: 10 Size Feet 40  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: A X & P, Inc Lic. # 3830  
Address: P O Box 1176, Independence, Kansas 67301

Company to plug at: Hour: \_\_\_\_\_ Day: 10 Month: 11 2006

Plugging proposal received from: J J Hanke

Company Name: A X & P Phone: 620-325-5212

Were: Remove pipe strings from well, perforate at selected intervals, and then fill from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 10 Month: 11 2006

Actual Plugging Report: The 1" pumping string was removed. The well was then perforated at 500', 250', 125', and 75'. A 1" cement string was lowered to TD and 15 sacks of cement spotted. The cement string was raised to 325' and the well filled to surface. A total of 85 sacks of portland cement were used to plug well.

**INVOICED**

DATE 1-21-09 RECEIVED  
KANSAS CORPORATION COMMISSION  
INV. NO. 2009061035 DEC 17 2008

Remarks: The original operator was Fred E. Woods and Associates.  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN

**PKG**