

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

This well was drilled in the 1960's
API NUMBER 15-205 - 19669-00-00
NE SE SE Sec/Twp/Rge Sec 29 T30S R16E
830 feet from south section line
650 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3830
Operator: A X & P, Inc.
Name & P O Box 1176
Address Independence, Kansas 67301
AB oil well XXXXXX Gas Well _____

Lease/Well# Unit 1 - Ellis #34P
County Wilson
Well Total Depth 800 feet
Production Pipe: 4 Size Feet 788
Surface Casing: 10 Size Feet 36
SWD Well/ Input Well _____ D & A _____

35

Other well as hereinafter indicated: _____

Plugging Contractor: A X & P, Inc Lic. # 3830

Address: P O Box 1176, Independence, Kansas 67301

Company to plug at: Hour: _____ Day: 10 Month: 11 2006

Plugging proposal received from: J J Hanke

Company Name: A X & P Phone: 620-325-5212

Were: Remove pipe strings from well, perforate at selected intervals, and then fill from btm to top thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part XXXXXX None _____
TECHNICIAN

Operations Completed: Hour: _____ Day: 10 Month: 11 2006

Actual Plugging Report: The 2" tubing was removed. The well was then perforated at 250', 125', and 75'. A 1" cement string was lowered to TD and 15 sacks of cement spotted. The cement string was raised to 500' and 10 sacks spotted. The cement string was raised to 250' and the well filled to surface.

A total of 78 sacks of portland cement were used to plug well. Gel spacers were used between plugs.

INVOICED RECEIVED
KANSAS CORPORATION COMMISSION

DATE 1-21-07 DEC 17 2008

INV. NO. 2009067035

Remarks: The original operator was Fred E. Woods and Associates.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KS

I partially observed this plugging

Signed:

Alan M. Dunning
TECHNICIAN

Handwritten initials/signature