

15-207-02104-00-00

To: STATE CORPORATION COMMISSION
 Wichita State Office Bldg. - PLUGGING SECTION
 130 S. Market, Room 2078
 Wichita, Kansas 67202

API NUMBER DRILLED IN 3/15/1956
 NW,SE,SW 1/4 Sec/Twp/Rge S.126-T.26S.-R.13E.
 1019 feet from south section line
 3637 feet from east section line

49.40

TECHNICIAN'S PLUGGING REPORT

Operator License # 33474

Operator: ARMADILLA OIL & GAS, LLC

Name & 2045 340 TH ST-MADISON

Address KANSAS 33474

AB oil well X Gas Well SWD Well/ Input Well D & A

Lease/Well# PRUE NO. 1

County WOODSON

Well Total Depth 1520' feet

Production Pipe: 4 1/2 Size Feet 1475

Surface Casing: 7" Size Feet 84'

Other well as hereinafter indicated:

Plugging Contractor: GEORGE SAGE Lic. # 5684

Address: P.O. BOX 12-VIRGIL, KS. 66870

Company to plug at: Hour: 8:00A.M. Day: 1 Month: 10 2008

Plugging proposal received from: GEORGE SAGE

Company Name: GEORGE SAGE Phone: 620-437-6009

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO 1475' THAT HAD BEEN CEMENTED
 IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG
 AT 1460', A 50' CEMENT PLUG AT 750', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM
 275' TO SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part None X

Operations Completed: Hour: 5:00P.M. Day: 3 Month: 10 2008

Actual Plugging Report: 2" PIPE WAS RAN INTO THE 4 1/2" CASING TO 1460'.

SIX SACKS OF CEMENT WERE PUMPED THROUGH THE 2' CASING TO 1460'. THE
 2" TUBING WAS PULLED TO 750'. 5 SACKS OF CEMENT WERE PUMPED THROUGH
 THE 2" TUBING TO 750' THE TUBING WAS PULLED TO 275'. CEMENT WAS PUMPED
 INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT
 SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Remarks: SPOT LOCATION ESTABLISHED VIA NAD 83 AS 1019' NSL & 3637' WEL.
 (If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

INVOICED Signed:
 DATE 1-21-09
 INV. NO. 2009061051

Clayton P. Titel
 TECHNICIAN

DEC 15 2008
 KANSAS CORPORATION COMMISSION
 CONSERVATION DIVISION
 WICHITA KS

RECEIVED
 COMMISSION