

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21355-01-00
Spot: SWSESE Sec/Twnshp/Rge: 24-28S-16W
50 feet from S Section Line, 990 feet from E Section Line
Lease Name: THORPE Well #: 1-24H
County: KIOWA Total Vertical Depth: 5910 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7.625	4865	0	WITH 215 SX CMT
SURF	13.38	345		WITH 350 SX CMT 19 2.08

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2008 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: 100 SX CMT DISPLACED TO 4100'. PERFORATE @ 1080'. CIRCULATE CMT TO SURFACE

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2008 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

HORIZONTAL LINER SET THROUGH MISSISSIPPI ZONE. ACO-1 INDICATED NO ALT 2 CEMENTING OR SQUEEZE JOBS. 12/8/08: PUMPED 300# HULLS & 100 SX CMT TO 4097'. 12/9/08: PERFORATE 7 5/8" CASING@ 1080'. DUG OUT SURFACE PIPE. FOUND CMT @ SURFACE IN 7 5/8"/13 3/8" ANNULUS. PUMPED DOWN 7 5/8" WITH WATER. TOOK INJECTION RATE @ 3 BPM @ 200#. SHUT DOWN DUE TO EQUIPMENT PROBLEMS & WEATHER. 12/10/08: PUMPED DOWN 7 5/8" CASING WITH 790 SX CMT @ 3-4 BPM @ 200# (NO LIFTING PRESSURE). RUN SLICK LINE & TAG TOC @ PERFS (1080'). 12/11/08: DUG OUT 13 3/8" SURFACE PIPE & CUT HOLE IN PIPE. FOUND CMT. PUMPED DOWN 7 5/8" CASING WITH 300# HULLS & 196 SX CMT TO FILL CASING FROM 1080' TO SURFACE.

Perfs:


INVOICED
DATE 1-21-09
INV. NO. 2009061049

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01



Signed

Stephen J Pfeifer
(TECHNICIAN)