

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCC OKT
Per Cap 5
381 330 feet from S Section Line, 3630 feet from E Section Line*

API Well Number: 15-195-21294-00-00
Spot: SWSESW Sec/Twnshp/Rge: 3-12S-21W
Lease Name: WIESNER J Well #: 4
County: TREGO Total Vertical Depth: 4090 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4088	0	125 SX
SURF	8.625	1024	0	550 SX

132.93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2008 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: ROLAND NYP Company: ALLIANCE WELL SERVICE INC. Phone: (785) 737-3242

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 200# hulls.
CIBP set at 3400'. Topped with 2 sxs cement. Put three point on to pull casing - no stretch in casing.
Perfed at 975'.
Operator elected all cement plug.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2008 12:35 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Alliance Well Service RIH to 2275'. Rigged to tubing - pumped 180 sxs cement with 200# hulls to circulate cement out 5 1/2" casing into pit.
Pulled tubing - topped 5 1/2" casing with 20 sxs cement - casing standing full of cement.
Rigged to 8 5/8" casing - pumped 20 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3922	3935		

INVOICED

DATE 1-23-09
INV. NO. 2009061076

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 07 2009
CONSERVATION DIVISION
WICHITA, KS

Acct.	Exp.	File	OK to Pay
GC			
KO			
JY			
PV			
CD			

DEC 29 2008

Remarks: ALLIED CEMENTING COMPANY-TICKET #34841.

Plugged through: TBG

District: 04

Signed  (TECHNICIAN) CM

PLS

PETROLEUM, INC.
800 R.H. GARVEY BLDG.
WICHITA, KS 67202

#4 "J" WIESNER

3-12-21W
SW SE SW

CONTR D N B. DRILG., INC.

CITY TREGO

GEOLOGIST KENNETH JOHNSON


FIELD KOHL WEST

Elev 2327 KB SPD 8/11/83

CARD ISSUED 10/6/83

W P 72 BOPD

MARM 3922-3935



API 15-195-21,294

LOG	Tops	Depth	Bottom
ANH		1749 +	578
B/ ANH		1799 +	528
TOP		3371-1044	
HEEB		3584-1257	
TOR		3605-1278	
LANS		3619-1292	
BKC		3856-1529	
MARM		3916-1589	
B/ MARM		3941-1614	
ARB		4041-1714	
RTD		4090-1763	

8 5/8 " 1022 / 550 SX; 5 1/2 " 4088/125SX
DST (1) 3916-3950 (MARM) / 15-30-60-120. REC 24' CL OIL, 56'
OCM, SIP 254-254#, FP 42-42 / 42-42#
MCT - CO, PF (MARM) 3922-35 W/1 SPF, AC 1000G, FRAC
20,000G GEL SW & 16,000# SD, SWB DWN & REC 2.32 BO /
30". T&R, POP, P 72 BOPD, 9/22/83

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS