

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-05189-00-00
Spot: SENENW Sec/Twnshp/Rge: 9-1S-34W
4290 feet from S Section Line, 2970 feet from E Section Line
Lease Name: TEXACO CAHOJ UNIT Well #: 11
County: RAWLINS Total Vertical Depth: 4240 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4227	0	130 SX
SURF	8.625	308	0	175 SX

137.80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/09/2008 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-1031

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 4% gel - 150# hulls.
Plug through tubing that was cemented in 5 1/2" production casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/09/2008 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 308' w/175 sxs cement.
5 1/2" production casing set at 4227' w/130 sxs cement.
PBTD 4210'. Casing holes squeezed with 250 sxs cement when 2 7/8" tubing string cemented inside of 5 1/2" production casing.
Holes at 2794'-3451'; 1524'-2325' and 1491'-1524'.
2 7/8" tubing string set at 3892'. Cement circulated to surface with 250 sxs.
Inserted pump - stuck in 2 7/8" tubing at 920'.
12-09-2008 - Connected to 2 7/8" tubing - pumped water to establish rate - returns from 5 1/2" production casing - pumped 10 sxs cement - cement to surface from 5 1/2" production casing.
Max. P.S.I. 700#.
Connected to 5 1/2" production casing - pressured to 1100#. 5 1/2" full.
Connected to 8 5/8" casing - pumped 20 sxs cement.
Max. P.S.I. 600#.

Perfs:

Top	Bot	Thru	Comments
4000	4195		

INVOICED

DATE 1-23-09
INV. NO. 2009061077

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 07 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: WELL ORIGINALLY KNOWN AS SIS #3. SWIFT SERVICES, INC. #15322.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

DEC 12 2008

PBT

THOS H ALLAN

#3 SIS

9-1-34W
SE NE NW

Contr. THOS H ALLAN

RAWLINS County

E 3111RB Comm. 9-11-59

Comp. 11-13-59

IP

156 BOPD

PHY POT

Tops	Depth	Datum
ST COR	2946	+165
TOP	3796	-685
LANS	3990	-879
TD	4240	-1129

Casing

8" 308
 5" 4228
 DST 4144-60/55", 90' G, 33' FR
 O, 30' OCM, 364' SW, BHP 1180#
 DD 4240: ACID 150: 69 GO & 161
 GW: PB 4219: PERF. 24/4191-95:
 SWB 27 BOPH, NW: PB 4210: SWB 26
 BOPH

CAHOJ POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS