

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23517-00-00  
Spot: SWNESESE Sec/Twnshp/Rge: 31-6S-22W  
960 feet from S Section Line, 430 feet from E Section Line  
Lease Name: SAND Well #: 1-31  
County: GRAHAM Total Vertical Depth: 3840 feet

Operator License No.: 32686  
Op Name: REILLY OIL COMPANY, INC.  
Address: PO BOX 277  
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	221		

124.80

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/01/2009 2:00 PM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: KIRBY Company: REILLY OIL COMPANY, INC. Phone: (785) 743-6774

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE  
Date/Time Plugging Completed: 01/01/2009 4:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

1st. Plug at 2005' w/25 sxs.  
2nd. Plug at 1230' w/100 sxs.  
3rd. Plug at 270' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 30 sxs.  
Mousehole with 15 sxs.

Perfs:

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 07 2009

CONSERVATION DIVISION  
WICHITA, KS

INVOICED  
DATE 1-23-09  
INV. NO. 2009061082

Remarks: S.O.S. CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

JAN 02 2009

Pat